



---

28.9 MW HFO Power Generation Solution / Guyana  
Power and Light Incorporated.

---

**PROJECT SUMMARY**

Guyana Power & Light Inc. / the Government of Guyana

Lot 91 Duke Street, Kingston. Georgetown. Guyana

**Contact details:** Telephone #: 225-4618

**Website:** [gpl.net](http://gpl.net)

**Prepared by:**  
Mr. Kesh Nandalall  
**Team Leader**

**2023-11-22**

## Table of Contents

Glossary of Terms: .....	3
<b>1. INTRODUCTION: .....</b>	<b>4</b>
2. PROJECT DESCRIPTION: .....	4
<b>2.1. Physical Location of Project:.....</b>	<b>5</b>
<b>2.2. Distance of project from stipulated locations .....</b>	<b>6</b>
<b>2.2.1. Settlement/Indigenous Communities.....</b>	<b>8</b>
<b>2.2.2. Land Dispute.....</b>	<b>8</b>
<b>2.2.3. General/Predominant Land use currently.....</b>	<b>8</b>
3. Baseline Information on the Physical, Ecological and Social Environment .....	9
<b>3.1. Physical Environment .....</b>	<b>9</b>
<b>3.1.1. Land.....</b>	<b>9</b>
<b>3.1.2. Drainage and Access Roads.....</b>	<b>9</b>
<b>3.1.3. Soil and Site Elevation.....</b>	<b>9</b>
<b>3.2. Stratigraphy.....</b>	<b>9</b>
<b>3.3. Topsoil (OH).....</b>	<b>10</b>
<b>3.4. Ground Water table conditions.....</b>	<b>10</b>
<b>3.5. Seismicity.....</b>	<b>10</b>
<b>3.6. Ecological Environment: .....</b>	<b>11</b>
<b>3.6.1. Land use.....</b>	<b>11</b>
<b>3.6.2. River use.....</b>	<b>11</b>
<b>3.6.3. Flora at the Earmarked project site.....</b>	<b>11</b>
<b>3.6.4. Biodiversity.....</b>	<b>12</b>
<b>3.7. Social Environment:.....</b>	<b>12</b>
<b>3.7.1. Human Habitation.....</b>	<b>12</b>
<b>3.7.2. Cultural and Traditional Use of project site.....</b>	<b>12</b>
<b>4. PROJECT LAYOUT:.....</b>	<b>12</b>
<b>4.1 Land Size.....</b>	<b>12</b>
<b>5. PROJECT DESIGN: .....</b>	<b>12</b>
<b>5.1. Technical Specifications.....</b>	<b>13</b>

5.2.	<b>Mechanical Specifications.....</b>	<b>16</b>
5.3.	<b>Water Treatment System.....</b>	<b>16</b>
5.4.	<b>Details of the Sludge and Oily Water Disposal system.....</b>	<b>16</b>
5.5.	<b>HFO Fuel System.....</b>	<b>17</b>
5.6.	<b>Lube Oil System.....</b>	<b>18</b>
5.7.	<b>Fire Fighting System.....</b>	<b>19</b>
5.8.	<b>Incinerator.....</b>	<b>19</b>
6.	<b>PROJECTSIZE: .....</b>	<b>20</b>
6.1.	<b>Capital Investment: .....</b>	<b>20</b>
6.2.	<b>Production Rate: .....</b>	<b>20</b>
6.3.	<b>Number of Employees projected for each stage: .....</b>	<b>20</b>
6.4.	<b>Source of Utility Services:.....</b>	<b>20</b>
6.5.	<b>Development stages from construction to closure:.....</b>	<b>20</b>
7.	<b>WASTE PRODUCTION AND MANAGEMENT:.....</b>	<b>22</b>
8.	<b>POTENTIAL ENVIRONMENTAL IMPACTS AND MITIGATION MEASURES: .....</b>	<b>28</b>
9.	<b>BORDERS AND BOUNDARIES:.....</b>	<b>34</b>
10.	<b>MINUTES OF PUBLIC CONSULTATION/ MEETINGS:.....</b>	<b>34</b>
11.	<b>PROPONENT WITH KEY STAKEHOLDERS: .....</b>	<b>34</b>
12.	<b>A NON-TECHNICAL SUMMARY:.....</b>	<b>35</b>

**Glossary of Terms:**

1. GTE-Gas to Energy
2. NGL- Natural Gas Liquids
3. CCGT- Combined Cycle Gas Turbine

4. NESC- National Electrical and Safety Codes
5. EPC-Engineering, procurement, and construction (contracts).
6. RFP – Request for Proposal

## 1. **INTRODUCTION:**

The Guyana Power and Light Incorporated is submitting this Project Summary to provide the Environmental Protection Agency with all the relevant information required for the processing of its Environmental Authorization Application for the construction and operation of a **28.9 MW HFO Power Generation Solution, Power Plant.**

This project will connect the Power Plant to the current National Grid, expand it and improve its overall reliability and stability.

## 2. **PROJECT DESCRIPTION:**

The **28.9 MW HFO Power Generation Solution, Power Plant** is geared at producing and transmitting electrical power generated by seventeen (17) 1.7MW Hyundai self-contained engines. Together, these engines will have an installed capacity of 28.9 MW, which will feed to the existing Columbia Substation via the installation of a 4160/69KV transformer. Additional support to the network will be supported via the installation of a 4160/13.8KV transformer. Both transformers will be located in the western boundary/direction of the Power Plant which will feed into the existing National Grid. The substation will further distribute electricity directly to customers within its vicinity (Mahaicony and Mahaica).

### **2.1. Physical Location of Project:**

The 28.9 MW HFO Power Generation Solution, Power Plant facility will be located at Colombia- Demerara Mahaica, Guyana. This project will occupy a total of Five (5) acres of land.

#### **Coordinates of Project Site:**

- 6° 38' 37.75" N
- 57° 52' 34.83" W
- 6° 38' 32.11" N
- 57° 52' 32.04" W
- 6° 38' 36.32" N
- 57° 52' 30.04" W
- 6° 38' 36.28" N
- 57° 52' 30.86" W

**2.2.Distance of project from stipulated locations**

*Figure 1: Google Satellite Imagery of Power Plant*





**2.2.1. Settlement/Indigenous Communities:**

There are no known Indigenous communities at the project site or surrounding areas.

**2.2.2. Land Dispute:**

There are no existing land disputes for the earmarked site.

**2.2.3. General/Predominant Land use currently**

The land at the site for the Power Plant is predominantly abandoned Rice cultivation plots (agricultural lands). As such, there are no residential, commercial, institutional, and industrial or mix use of the parcel of land earmarked for the project site.

**Table 1: Proximity to various locations/ Sensitive receptors**

	<50 meters	50m-100m	101m-500m	501m-1000m	>1km
Sensitive ecosystems e.g. Wetlands/Mangroves	Nil	Nil	Nil	Nil	Nil
Protected Areas	Nil	Nil	Nil	Nil	Nil
Major Water Courses	Nil	Nil	Nil	Nil	Nil
Threatened or endangered flora and fauna	Nil	Nil	Nil	Nil	Nil
Residences	√	√	√	√	√
Place of Worship	Nil	Nil	Nil	Nil	Nil
Schools	Nil	Nil	Nil	Nil	Nil
Hospitals	Nil	Nil	Nil	Nil	Nil
River / Sea Defence	Nil	Nil	Nil	Nil	Nil
Other – State					

### **3. Baseline Information on the Physical, Ecological and Social Environment**

#### **3.1. Physical Environment**

##### **3.1.1. Land:**

The land at the site for the Power Plant is predominantly abandoned Rice cultivation plots (agricultural lands) and is vegetated with overgrown grass and shrubs.

##### **3.1.2. Drainage and Access Roads**

Drainage trenches or canals are to be located East, South and West of the site beyond the embankments, which impound the land. The access road is situated to the West of the facility.

##### **3.1.3. Soil and Site Elevation**

The project site is located within the 'Low Coastal Plain' Geographic Region of Guyana. The Low Coastal Plain is a South-East/ North-West, 434 km/270 mile long stretch which varies in width along Guyana's coast and is estimated to be 1.5m below high tide level. Thin layers of Pagasse (organics) cover soft clays in some areas and overlie two distinct coastal Clay formations, the recent Holocene dated Demerara formation and the older Pleistocene dated Coropina formation. The Demerara formation consists of shallow, very soft to soft silty clays and clays while the Coropina formation are described as deep, stiff, grey and mottled clays.

#### **3.2. Stratigraphy**

Subsurface stratigraphy was described during the drilling exercise based on Standard Penetration Test resistance values (N values) and visually and physically inspected samples on site using aspects of ASTM D2488 for describing and identifying soils.

### **3.3. Topsoil (OH)**

Topsoil was dark brown silty clays with organic matter. Very soft to soft Silty Clay (CH/MH) Brown- Grey silty clays with distinct lenses and pockets of silt were encountered in each borehole from depths of 0.5 m to approximately 20 m.

Standard penetration tests conducted generally resulted in resistance (N values) of less than 4. In some cases in these weak soils, no standard penetration resistance (N value) was recorded as the weight of the Standard penetration test hammer sank the split barrel sampler without blows being applied.

Medium Silty Clay (CH/MH) Grey silty clays were encountered in each borehole from depths of 20 m to approximately 25 m with Standard penetration test resistance (N values) of less than 8.6.4 Very Stiff Silty Clays - Hard Mottled Clay (CH).

A significant increase in penetration resistance was encountered between 25m to 30m in each borehole where a progression from Light grey- grey silty clays to hard mottle clays with traces of blue and orange colour was encountered. Standard penetration tests conducted generally resulted in resistance (N values) of more than 30.


### **3.4. Ground Water table conditions**

Immediate ground water levels in boreholes were not recordable at the time of this investigation. The site was covered by 8"- 12" of surface water because of recent rainfall and lack of drain.

### **3.5. Seismicity**

Peak Ground Acceleration data depicted on the OAS Seismic Hazard Map of Guyana ranges between 45-70 gals in the project area. According to the Global Earthquake Model PGA scale also, Guyana has a low vulnerability to seismic activities. Guyana is located on the South American Plate, South of the Caribbean and South American plate boundary.

**Figure 3: OAS Seismic Hazard Map-Guyana**



### **3.6. Ecological Environment:**

#### **3.6.1. Land use**

The land previously used for agricultural purposes- rice cultivation is imploded and approximately 8” -12” inundated which remained stagnant after periods of rainfall.

#### **3.6.2. River use**

There are no rivers located within the vicinity of the Project.

#### **3.6.3. Flora at the Earmarked project site:**

The land at the site is populated with grass and shrubs.

#### **3.6.4. Biodiversity:**

There is no critical biodiversity expected at this area and the land is of low value to most wildlife.

#### **3.7. Social Environment:**

##### **3.7.1. Human Habitation:**

Currently, there is no human habitation at the Colombia Project site. The land is unoccupied, however there are some residential properties located on the Northern section opposite the Project site.

##### **3.7.2. Cultural and Traditional Use of project site:**

There are no known cultural or traditional uses of the proposed site.

#### **4. PROJECT LAYOUT:**

**4.1 Land Size:** The approved land size for the Project is approximately Eight (8) Acres.

#### **5. PROJECT DESIGN:**

The project will utilize Seventeen (17) Himsen-Hyundai Engines, along with supporting structures and components, which will feed to the existing Columbia substation via the installation of a 4160/69KV transformer. Additional support to the network will be supported via the installation of a 4160/13.8KV transformer; equipment will together form a Power Generating facility with an output of 28.9 MW.

## 5.1. Technical Specifications

**Figure 4: Engine technical specifications**

### TECHNICAL DETAILS

#### ENGINE

<b>Engines:</b>	17- 1700 KW Himsen 9Hz1/32 Generator
<b>Year :</b>	2016
<b>Manufacturer :</b>	Himsen
<b>Fuel Type :</b>	HFO
<b>KW :</b>	1700
<b>Hz :</b>	60
<b>Voltage :</b>	4160
<b>RPM :</b>	900
<b>Hours :</b>	6700



#### HEAT RATE

Specific Consumption at Engine & Heat Rate

100% Load	Unit	900rpm	1000rpm
Fuel Oil Consumption	g/kWh	183	185
Lube oil consumption	g/kWh	0.6	0.6
Heat Rate	KJ/kWh	7.814	7.899
Diesel Oil or Heavy Fuel Oil	KJ/kWh	8.313	8.404

#### Dimensions

Speed	Cyl	Dimensions			Dry Mass (ton)	
		L	W	H	Genset	Total weight
900/1000 rpm	6	12	2.4	3.4	28.1	42
	8	12	2.4	3.4	29.1	48
	9	12	2.4	3.4	31.7	5



- |                               |                          |
|-------------------------------|--------------------------|
| (1) Engine                    | (4) Generator            |
| (2) Control panel             | (5) Enclosure            |
| (3) Radiator                  | (6) Exhaust gas silencer |
| (7) Ventilator or exhaust fan |                          |

**Figure 5: Engine technical specifications**

**GENERATOR**

Generator/Alternator and transformer(s) technical parameters  
Principal Data for H21/32 Gen-Set

Type of Engine	4-stroke, vertical, direct injection single acting and trunk piston type with turbocharger and inter-cooler				
Cylinder Configuration	in - line				
Number of Cylinder	5 - 6 - 7 - 8 - 9				
Rated Speed	rpm	720	750	900	1000
Power per Cylinder(kW)	kW	160	160	200	200
Cylinder Bore(mm)	mm	210			
Piston Stroke(mm)	mm	320			
Swept Volume per Cylinder	dm <sup>3</sup>	11.1			
Mean Piston Speed	m/s	7.7	8.0	9.8	10.7
Mean Effective Pressure	bar	24.1	23.1	24.1	21.7
Compression Ratio	17:1				
Direction of Engine Rotation	Clockwise Viewed from Generator Side (Non-Reversible)				
Cylinder Firing Order	5H21/32	1 - 2 - 4 - 5 - 3			
	6H21/32	1 - 4 - 2 - 6 - 3 - 5			
	7H21/32	1 - 2 - 4 - 6 - 7 - 5 - 3			
	8H21/32	1 - 3 - 5 - 7 - 8 - 6 - 4 - 2			
	9H21/32	1 - 3 - 5 - 7 - 9 - 8 - 6 - 4 - 2			

System	Name Descriptions	Normal Operating Range at Rated Power	Alarm Setting	Autostop of Engine	Remarks
Control Speed	Engine speed	Rated Speed (rpm)		113%(1 <sup>st</sup> ) 115%(2 <sup>nd</sup> ) of rated speed	
		720/750/900/1000			
Fuel Oil System	Fuel oil leakage level		High level		
	Fuel oil pressure inlet engine (for Continuous HFO operation)	4.0 ~ 6.0 bar (MDO)			
		8 <sup>±2</sup> bar (HFO)	P <sub>HFO</sub> < 6.0 bar		
	Fuel oil pressure inlet engine (for Continuous MDO operation)	7.0 ~ 8.0 bar (MDO)	P <sub>MDO</sub> < 6.0 bar		
Fuel oil temperature inlet engine	30 ~ 45 °C (MDO)				
	110 ~ 140 °C (HFO)	150 °C			
Lub. Oil System	Lub. oil pressure drop-filter	0.1 ~ 1.0 bar	> 1.5 bar	2.0 bar (if applied)	
	Lub. oil pressure inlet engine after filter	4.0 ~ 5.0 bar	< 3.5 bar	3.0 bar	
	Lub. oil temperature inlet engine	60 ~ 70 °C	> 80 °C		
	Lub. oil pressure inlet TC	2.0 ~ 4.0 bar	1.5 bar		
	Oil mist detector (option)		High level	High level	
	Lub. oil level in base frame		Low/high level		
	Pratubricating oil level		Low level		
Cooling Water System	LT water pressure inlet engine	1.5 ~ 4.5 bar	< static+0.4 bar		
	LT water temperature inlet engine	30 ~ 40 °C	> 45 °C		
	HT water pressure inlet engine	2.5 ~ 4.5 bar	< static+0.4 bar		
	HT water temperature outlet engine	75 ~ 85 °C	> 90 °C	>95 °C	
Combustion Gas System	Cylinder pressure	Max. ~ 200 bar	-	-	Refer to shop test result
	Deviation from average of cylinders	Max. ±5bar			
	Charge air pressure after cooler	2.5 ~ 3.2 bar			
	Charge air temperature after cooler	35 ~ 55 °C			
	Deviation from average of cylinders	±50 °C	±70 °C		
	Exh. gas temperature inlet TC	420 ~ 550 °C	> 580 °C		
	Exh. gas temperature outlet TC	250 ~ 380 °C	> 450 °C		
Compressed Air System	Compressed air inlet pressure	5 ~ 7 bar	< 4.5 bar		For 5,6 cyl.
		8 ~ 10 bar	< 7.5 bar		For 8,9 cyl.

## **5.2.Mechanical Specifications:**

Below are the details on the following:

1. Water treatment unit(s),
2. Oily water treatment,
3. Maintenance water tank,
4. HFO buffer tank, LFO tank
5. Containment walls for all fuel storage tanks,
6. Pumping facilities for filling and discharge of HFO bulk storage tank for a complete tank farm facility.

Water Details on water treatment unit(s) – “dependent on the quality of the extracted water well” COLOMBIA TEMP. Power Plant Station will be utilizing the following sources of water for the processes on site: Ground water (primary source). Treated water will be utilized for the following services and/or pieces equipment: Heavy fuel oil (HFO) Purifier Unit Oily Water Separator Cooling Water Expansion Tanks T/C Cleaning Nozzle HFO Treatment Unit (HTU) for LO Purifier Unit Boiler.

## **5.3.Water Treatment System:**

The water treatment unit will utilize of the following sub-components for water treatment:

1. Filters
2. Pumps
3. Tanks

## **5.4.Details of the Sludge and Oily Water Disposal system**

The COLOMBIA TEMP. Power Plant Station will utilize a wastewater and waste products disposal system for all process waste. The drainage network consists of various trenches and pits throughout the site for waste processing products (Oily water; HFO; LO; etc.) piped to a storage tank and then treated in oily water separator system for additional treatment and sludge disposal.

**The Sludge and Oily Water Disposal system consists of the following main components:**

1. Drainage Network (Inclusive of Pits; Submersible Pumps)
2. Point of Delivery/Unloading (Multiple ports)
3. Pump station Unit - Sludge Unloading pump.
4. Pump station Unit – Sludge Transfer Pump
5. Oily Water storage Tank
6. Sludge Storage Tank
7. Oily Water Interceptor
8. Electric Heaters

**5.5. HFO Fuel System**

Details on the Fuel Oil system: The COLOMBIA TEMP. Power Plant Station will utilize HFO as the primary and sole source of fuel. HFO will be delivered to site via tankers and stored for processing and utilization in bulk storage tanks housed within a tank farm. The facility will be provided with an on-site tank capacity of thirty (30) days to support a minimum plant utilization of approximately fourteen (14) MDU units at any point in time.

**The Fuel oil system consists of the following main components.**

1. Point of supply (delivery point – multiple ports)
2. Pump station Unit – HFO unloading pump.
3. Pump station Unit – HFO transfer pump.
4. Pump station Unit – HFO supply pump
5. HFO Storage Tank complete with storage heater
6. HFO Purifier Unit
7. HFO Settling Tank
8. HFO Service Tank

The HFO Treatment unit (HTU) provides fuel oil to the engines within acceptable parameters as well as treats the Lube Oil (LO) via the Lube Oil purifier unit.

**The HFO treatment unit consists of the following main components:**

1. LO Purifier
2. Purifier Feed Pump
3. Sludge Pump
4. Sludge Tank
5. Control Panel
6. Viscosity Controller
7. FO Booster Unit
8. FO Steam Heater
9. Nozzles

The HFO Treatment unit will be housed within a forty (40) foot container complete with Ventilation, lighting and communication. The COLOMBIA TEMP. Power Plant Station will be outfitted with two (2) HTU that will supply the MDU units.

### **5.6.Lube Oil System**

Details on the Lubricating Oil system: The COLOMBIA TEMP. Power Plant Station will be outfitted with a lubricating oil system intended to support the internal lubricating oil system of the MDU. Given the nature of the operations, the system allows for the loading, storage, distribution and Purifying of the LO. The engine has its own internal lubricating oil system with wet type oil sump. Most of the oil passages are incorporated into the engine components and the equipment's of the system are mounted directly on feed block without pipe connections.

**The Lubricating oil system consists of the following main components.**

1. Point of supply (Delivery Point – Multiple ports)
2. Pump station Unit – LO Unloading pump.
3. Pump station Unit – LO transfer pump

4. LO Storage Tank 53
5. LO Used Tank
6. LO Purifier Unit (Internal HTU)

#### **5.7. Fire Fighting System**

Details on the Fire fighting system: The COLOMBIA TEMP. Power Plant Station overall fire fighting system shall consist of a combination of the following:

1. Fire Water Pumps (Electric Fire pump and Diesel Driven Fire engines rated for 1000 GPM minimum)
2. Fire water reservoir tank (120,000 Gal or Two (2) hours)
3. Hydrant system
4. Hose Cabinets
5. Deluge system for Tanks (Cooling)
6. Potable fire fighting extinguishers at various (CO<sub>2</sub>, foam and dry powder)

**The following systems will be specifically protected by the fire fighting system:**

1. MDU's
2. Exhaust systems
3. Fuel storage and distribution systems
4. Electrical installations
5. Working/Office spaces

#### **5.8. Incinerator**

The **Inciner8** Incinerator's bulk capacity, advanced secondary chamber technology and provision for automatic waste loading offer an effective and sustainable waste disposal method for several industries that produce a high daily volume of waste. The system delivers clean and tidy effective waste solutions, making the investment invaluable.

#### **Capacity:**

Industrial waste <1000 kg per day

6. **PROJECTSIZE:**

**6.1.Capital Investment:**

The estimated capital investment for the establishment of the 28.9 MW Power Plant at Colombia is currently pegged at 27.5 Million USD.

**6.2.Production Rate:**

The project will distribute 28.9 MW of electricity generated from the Colombia Power Plant.

**6.3.Number of Employees projected for each stage:**

Information will be provided once made available by contractor.

**6.4.Source of Utility Services:**

Guyana Water Incorporated (GWI) will supply water to the various Substations and the Guyana Power & Light Inc. (GPL) will supply Electrical power.

**6.5.Development stages from construction to closure:**

The planned activities associated with all development stages from construction to closure are, but not limited to, the following:

**Table 2: The establishment of the 28.9MW Power Plant will include the following stages of development:**

<b>STAGE 1- Early Work</b>	<b>STAGE 2- Construction of 28.9MW Power Plant</b>	<b>STAGE 3- Operation</b>
Site preparation- Land Clearing (Removal of Trees and vegetation at project sites).	Civil/Construction works for establishing a 28.9 MW Power Generating facility.	Pre-Commissioning of 28.9 MW Power Generating facility.
Excavation may be required in some area as part of site preparation	Installation and assembling of Equipment, Transmission lines connecting to Substation and transmission network.	Commissioning of 28.9 MW Power Generating facility.
Establishing drainage networks where necessary	Connecting of all Transmission Lines to the appropriate Substations	Control via Contracted Operator and distribution via GPL's Transmission and Distributions Dept.

**7. WASTE PRODUCTION AND MANAGEMENT:**


**Table 3: Waste during construction of 28.9 MW Power Plant**

<b>Waste Type</b>	<b>Source</b>	<b>Management/ Treatment</b>	<b>Quantity of Waste Generated</b>
Gray water	Portable sinks on worksite	Gray water and Black water (Sewage) will be stored in tanks on site until removal via local waste disposal provider at various construction sites.	To be determined
Black Water(Sewage)	Portable toilets on worksite	Gray water and Black water (Sewage) will be stored in tanks on site until removal via local waste disposal provider at various construction sites.	To be determined
Runoffs from construction process(Sediments)	Land preparation process, excavation	<p>During the course of construction, the contractor will perform, construct, and maintain on-site soil erosion and sediment control measures.</p> <p>Adequate drainage will be designed for the site to minimize run off</p> <p>Drainage systems will be monitored and frequently maintained</p> <p>Adequate temporary sanitary facilities will be provided for workers on-site</p> <p>Frequent collection of waste generated by sanitary facilities will be done by an EPA approved contractor</p>	To be determined

Solid waste	Generated from workers onsite	<p>Waste Generated by Workers during construction phase</p> <p>An EPA approved contractor will collect all waste generated on site.</p> <p>The site will be provided with an adequate number of bins for the disposal of domestic waste</p> <p>Burning of waste on-site will be prohibited</p>	To be determined
<b>Waste during operation of Power Plant</b>			
Gray water	Portable sinks on worksite	Gray water will be directed to onsite drainage system and collection pits	To be determined
Black Water(Sewage)	Portable toilets on worksite	Black water (Sewage) will be directed to onsite sewage system.	To be determined
Storm Water run-off	Rainfall	All storm-water will be directed to established drainage system of the facility	To be determined
Hazardous Waste (Sludge)	By-product from the treatment of HFO Fuel	<p>The Hazardous Waste (Sludge) will be directed to an Oily Water Tank, which will then be transported to the onsite "Oily Water Separation Unit".</p> <p>Whereby the oil waste will be separated and sent to an onsite Sludge Concentration Tank and the separated water will be discharged via the effluent discharge points of the facility.</p>	To be determined

Oily Rags	Used during maintenance activities and others	All oily rags generated will be incinerated via the facility's onsite Incinerator.	Approximately 100 lbs. per month
Filters	By-Product from Operation.	All filters will be removed via an EPA authorized Hazardous waste disposal company.	To be determined
General non-hazardous waste	Generated by operators and other staff Control rooms/ security etc.	Utilizing external registered waste disposal company.GPL currently utilizes Cevons Waste Disposal Services-.	To be determined

**Figure 6: Project Duration:**



ID#	Task Name	Predecessors	Duration	Start	End
41	<b>Portable Fire Extinguisher Locations - Plant and Details</b>		15 days	01/15/2020	01/30/2020
42	Design & Submission	34	13 days	01/15/2020	01/28/2020
43	Revision and approval by End User	42	2 days	01/28/2020	01/30/2020
44	<b>ELECTROMECHANICAL DESIGN</b>		20 days	01/15/2020	02/04/2020
45	<b>DOCUMENTS</b>		3 days	01/15/2020	01/18/2020
46	Submission of Manufacturer Equipment/Material Technical Specifications	2	3 days	01/15/2020	01/18/2020
47	<b>DESIGN &amp; DRAWINGS</b>		17 days	01/15/2020	02/01/2020
48	Equipment General Layout		17 days	01/15/2020	02/01/2020
49	Design & Submission	46	16 days	01/15/2020	01/31/2020
50	Client Review	49	1 day	01/31/2020	02/01/2020
51	<b>Equipment Assembly and Details</b>		17 days	01/15/2020	02/01/2020
52	Design & Submission	46	16 days	01/15/2020	01/31/2020
53	Client Review	52	1 day	01/31/2020	02/01/2020
54	<b>Support Structures Assembly and Details</b>		17 days	01/15/2020	02/01/2020
55	Design & Submission	46	16 days	01/15/2020	01/31/2020
56	Revision and approval by End User	55	1 day	01/31/2020	02/01/2020
57	<b>Equipment &amp; Support Structure Grounding Assembly &amp; Details</b>		17 days	01/15/2020	02/01/2020
58	Design & Submission	46	16 days	01/15/2020	01/31/2020
59	Revision and approval by End User	58	1 day	01/31/2020	02/01/2020
60	<b>Lightning Protection System Details</b>		17 days	01/15/2020	02/01/2020
61	Design & Submission	46	16 days	01/15/2020	01/31/2020
62	Revision and approval by End User	61	1 day	01/31/2020	02/01/2020
63	<b>Exterior Lighting System</b>		17 days	01/15/2020	02/01/2020
64	Design & Submission	46	16 days	01/15/2020	01/31/2020
65	Revision and approval by End User	63	1 day	01/31/2020	02/01/2020
66	<b>PROCUREMENT</b>		60 days	01/15/2020	03/14/2020
67	<b>CIVIL</b>		60 days	01/15/2020	03/14/2020
68	Earthworks Material	2	60 days	01/15/2020	03/14/2020
69	Prefabricated Material	68SS	60 days	01/15/2020	03/14/2020
70	<b>MECHANICAL</b>		60 days	01/15/2020	03/14/2020
71	Mechanical Equipment	68SS	60 days	01/15/2020	03/14/2020
72	<b>ELECTROMECHANICAL</b>		60 days	01/15/2020	03/14/2020
73	Support Structures	68SS	60 days	01/15/2020	03/14/2020
74	Electrical Equipment	68SS	60 days	01/15/2020	03/14/2020
75	<b>GENERATION PLANT &amp; AUX COMPONENTS</b>		60 days	01/15/2020	03/14/2020
76	<b>CONSTRUCTION</b>		160 days	01/15/2020	05/13/2020
77	<b>PRELIMINARIES</b>		8 days	01/15/2020	01/23/2020
78	Mobilization-Establish Camp, Site Office, Temporary Facilities	2	5 days	01/15/2020	01/20/2020
79	Site Preparation	78	3 days	01/20/2020	01/23/2020
80	<b>CIVILWORKS</b>		152 days	01/15/2020	05/06/2020

ID	Task Name	Predecessors	Duration	Start	End
81	Construction of Perimeter fence, base wall and gates	77	152 days	5/1	7/8
82	Construction of Foundations & Plinths	81SS	152 days	5/1	7/8
83	Construction of Guard Booth, Pump Room	81SS	152 days	5/1	7/8
84	Installation of Tams	81SS	152 days	5/1	7/8
85	Installation of Containers	81SS	152 days	5/1	7/8
86	Construction of Substation Roadways	81SS	152 days	5/1	7/8
87	<b>ELECTROMECHANICAL WORKS</b>		<b>90 days</b>		
88	Installation of Support Structures	77, 86FS-5 days	90 days	5/1	7/8
89	Installation of Busbar system	88SS	90 days	5/1	7/8
90	Installation of Electrical Power Equipment, Transformer, Engines	88SS	90 days	5/1	7/8
91	Interconnection of equipment with conductors	88SS	90 days	5/1	7/8
92	Installation and termination of all power and multicores cables	88SS	90 days	5/1	7/8
93	Installation of lighting pole and light fixtures	88SS	90 days	5/1	7/8
94	<b>COMMISSIONING</b>		<b>20 days</b>		
95	Commissioning & Testing	86	20 days	5/1	6/3
96	<b>ENERGIZATION (PROJECT COMPLETION DATE)</b>		<b>0 days</b>		
97	<b>Payment Schedule</b>		<b>180 days</b>		
98	Advance Payment [15%]	4	0 days	5/1	5/1
99	Interim Payment #1 [35%]	98FS+30 days	0 days	6/3	6/3
100	Interim Payment #2 [20%]	99FS+30 days	0 days	7/8	7/8
101	Interim Payment #3 [15%]	100FS+30 days	0 days	8/12	8/12
102	Final Payment [15%]	96, 101	0 days	11/25	11/25

### 1. Decommissioning plan:

Unknown at this stage of the Project

**8. POTENTIAL ENVIRONMENTAL IMPACTS AND MITIGATION MEASURES:**

**Table 4: Potential Environmental impacts from construction and operation of proposed project and Mitigation measures**

<b>Receptors</b>	<b>Source of impact</b>	<b>Possible effects of impact on human life and Environment</b>	<b>Mitigation measures</b>
<b>Construction of 28.9 MW Power Plant</b>			
Soil	Land clearing and excavation for the construction of Power Plant and supporting components	Erosion and Compaction, Earthworks/ land clearing will disturb soils and ecosystems.	Adequate drainage will be developed for relevant sites and the Implementation of re-vegetation measures in critical areas where necessary.
Water Quality (Ground and Surface Water).	Earthworks related to site preparation can result in the discharge of sediment to canals or other drainage features	Runoffs from site Preparation can lead sedimentation in drains, canals and trenches. This can affect aquatic ecosystems and can affect human health. The Project has the potential to affect groundwater quality.	Adequate drainage will be designed for the site to minimize runoff. Drainage systems will be monitored and frequently maintained. Adequate temporary sanitary facilities will be provided for workers on-site. Frequent collection of waste generated by sanitary facilities will be done by an EPA approved contractor.
Air Quality	Emission from site	Dust Generation and Exhaust	Covering of Stockpiles to

	<p>preparation activities to facilitate the construction of Power Plant and supporting components.</p> <p>Emissions from Equipment/ Machinery and Vehicles.</p>	<p>Emissions may affect Ambient Air Quality at the Project area on localized basis. Combustion from hydrocarbons can contribute to greenhouse gas emissions</p>	<p>minimize dust generation, Suppressing dust from construction, stockpiles and increased vehicular traffic by sprinkling water, Consideration of wind direction when stockpiling construction materials, and Orientation shall avoid downwind residences or sensitive locations.</p> <p>Regular maintenance of vehicles and on-site construction equipment</p>
<p>Noise and Vibration</p>	<p>Operation of Equipment and Machinery during construction</p>	<p>Noise Pollution may pose a nuisance to the tranquillity of the environment, and may have an impact on human health. Further, Increase Noise Pollution can affect wildlife (E.g. nesting birds etc.)</p>	<p>Noise and vibration shall be to control and limit noise and vibration level from activities at the source by the use of Best Practicable Means (BPM) and ensuring compliance with relevant legislation.</p> <p>Additionally, the use of ear plugs or ear muffs for specific activities by workers</p> <p>Activities will be limited to daylight hours, where practicable.</p>

Flora and Fauna	Land Clearing for the construction of the power plant will require some amount of vegetation clearance.	Disturbance of Ecosystems, wildlife breeding/ feeding patterns, increased erosion and habitat destruction are all potential risk associated with the removal of small trees and vegetation at the project site.	Where practicable, trees, shrubbery, topsoil, grass, and other landscape materials shall be replanted/ reappplied.
Solid waste pollution	Waste Generated via site preparation activities and from workers during site preparation.	Garbage Pollution	An EPA approved contractor will collect all domestic waste generated on site.  The site will be provided with an adequate number of bins for the disposal of domestic waste  Burning of waste on-site will be prohibited

**Potential Environmental impacts from operation of proposed project**

Soil	Spillages from plant operation:  Potential Spillage of Fuel during Transfer Processes	Contamination of soil during Plant operating activities may lead to ground and surface water contamination, clogging of soil, thus preventing water and air movement required by plant and soil organisms, and it may also	The facility will have a designated fuel loading zone, which will be constructed with a concrete base and a collection pit for all potential spillages. This pit will be directed to the oily water
------	---	--	---

	<p>Spillage via Effluent Discharge in the event of malfunctioning Oily Water Separators</p> <p>Movement of Sludge in the event of malfunctioning incinerator.</p> <p>Spillage during maintenance.</p>	<p>lead damages to soil ecosystems.</p>	<p>separator.</p> <p>Contractors will be required to provide a procedure for fuel transfer, with adequate mitigating and preventative measures to spillages.</p> <p>Contractors will also be required to have spill kits on fuel trucks and onsite during fuel transfer processes.</p> <p>The contractor will be required to provide an Emergency Response Plan for potential spillages and evidence that all relevant personnel received training on the ER plan and Fuel transfer Procedure.</p> <p>The facility will be fitted with an Oily Water Separator, whereby all effluent will pass through prior to discharge into environment.</p> <p>An Effluent Monitoring schedule will be established and regular effluent monitoring will be conducted.</p> <p>The Oily Water Separator will</p>
--	---	---	--

			<p>be maintained according to schedule.</p> <p>The Incinerator will be maintained in accordance with manual and further sludge samples will be tested to ensure compliance with Incinerator requirement.</p> <p>All Power Plants and areas with Hazardous waste and fuel will be supplied with Spill Kits.</p> <p>All relevant staff onsite will be trained on Emergency response in the event of a spillage.</p>
Water Quality (Ground and Surface Water).	Spillages via effluent discharged from the facility.	Contamination of ground water sources Pollution of surface water. Damage to ecosystems.	<p>All run-offs and storm water will be redirected to an established drainage system.</p> <p>The facility will be fitted with an Oily Water Separator, whereby all effluent will pass through prior to discharge into environment.</p> <p>An Effluent Monitoring schedule will be established and regular effluent monitoring</p>

			<p>will be conducted.</p> <p>The Oily Water Separator will be maintained according to schedule.</p>
Air Quality	<p>Emissions from Generating Engines and Incinerator during operation.</p>	<p>Emissions may affect Ambient Air Quality at the Project area. Combustion from hydrocarbons can contribute to greenhouse gas emissions.</p>	<p>Ensure compliance with environmental regulations by monitoring and minimizing emissions from the generating Engines.</p> <p>Monitor and analyze the performance of the generating engines to identify opportunities for improvement in scheduling, maintenance, and efficiency.</p>
Noise	<p>Operations of Generating Engines and Incinerator.</p> <p>Fire Drills.</p>	<p>Persistent noise may affect the tranquillity of the environment for residents in close-proximity of the Power Plant.</p>	<p>The engines will be housed in noise attenuating containers.</p> <p>The engines are fitted with mufflers to minimize noise emissions.</p> <p>Employees will be provided with noise protective PPE.</p> <p>The facility will comply with all Regulatory noise compliance requirements (Noise Limits).</p> <p>Fire Drills occur for a period of</p>

			2 minutes, quarterly. Therefore, it pose no significant noise pollution.
Solid waste pollution	Waste Generated from operators on substation.	Garbage Pollution	An EPA approved contractor will collect all domestic waste generated on site.  The site will be provided with an adequate number of bins for the disposal of domestic waste  Burning of waste on-site will be prohibited

9. **BORDERS AND BOUNDARIES:**

The Project does not cross any Borders or Boundaries.

10. **MINUTES OF PUBLIC CONSULTATION/ MEETINGS:**

Given the current stage of the Project such as public hearing/activity is still to be conducted.

11. **PROPONENT WITH KEY STAKEHOLDERS:**

Given the current stage of the Project such as public hearing/activity is still to be conducted.

**12. A NON-TECHNICAL SUMMARY:**

This process starts with the use of Heavy fuel oils (HFO), taken from a bulk storage tank, pumped into a buffer tank, fed through HFO separators and then to a daily service tank for use by each of the Hyundai engine to generate power.

The engine(s), then utilize this fuel by injecting small amounts, at precise times within a cylinder. The cylinder contains compressed air, thus the combination of the air/ fuel mixture results in a spark that produces heat; this heat energy moves several pistons up and down. The up and down movement of these pistons is called a stroke and the consistent strokes of the engine's pistons generates electrical energy or Electricity. This Electrical power is fed to a grid, and then transmitted to a substation and subsequently to consumers.